

Electricity Supply Board
 One Dublin Airport Central
 Dublin Airport
 Cloughran
 Co. Dublin

08 April 2020

Our Reference
 PR-427640

Preliminary Site Assessment - Site 57 Inchicore – Poolbeg 220 kV

AECOM Ireland Limited (AECOM) completed a Preliminary Site Assessment (PSA) of a cable fluid leak on a 220 kV underground electrical cable running from Inchicore to Poolbeg in Dublin City on behalf of Electricity Supply Board (ESB). The location of the leak is on the Grand Canal southern tow path in Inchicore, Dublin 8. The PSA report was issued on 08 April 2020 (Report Ref. PR-427640_ACM_RP_ENV_059_0). AECOM understand that ESB has undertaken these works on behalf of ESB Networks.

It is estimated that 1,137 litres of cable fluid (Linear Alkyl Benzene (T 3788)) was released between May 2004 and July 2004. Due to its high biodegradability, it is considered that LABs are of less concern for adverse environmental impact than other hydrocarbon fluids. A summary of the source audit findings is as follows:

Table A Area of Potential Environmental Concern

Number	APEC	Potential Contaminants of Concern	Potential Media Impacted
1	Leak at (57) Inchicore – Poolbeg 220 kV (May 2004 – July 2004)	LABs	Soil Groundwater Ground Gas

The preliminary CSM developed for the site looked at potential source-pathway-receptor linkages identified during the assessment works and identified a moderate risk to site users due to the potential for ground gas generation resulting from degradation of LAB NAPL (if present).

A low/moderate risk was identified to groundwater due to potential impact to groundwater chemistry from the presence of NAPL.

Potential risk to the Grand Canal was considered to be low given that canals are generally lined with impermeable materials which would prevent the migration of NAPL into the canal from groundwater or via preferential flow pathways.

Risks associated with other potential source-pathway-receptor linkages were considered to be low.

The PSA is preliminary in nature as it was based on an evaluation of qualitative data sources, meaning that identification of potential risk does not necessarily indicate a risk to a receptor, rather that further assessment may be required.

Given that potential risks were identified in the PSA, it is considered that intrusive site assessment is required to further assess assumptions made in the preliminary CSM and potential source-pathway-receptor (SPR) linkages. The findings of the PSA should form the basis of the scope of work for further detailed site assessment (DSA), and it is recommended that an iterative approach be adopted for intrusive assessment works. Given that the leak location has been confirmed, the first (exploratory) step in the DSA process would be to assess soil and groundwater conditions (as well as

the presence of NAPL) through the excavation of slit trenches / trial pits in the vicinity of the leak location. A key aspect of these investigation points would be to expose the cable backfill materials to assess if they have acted as a migration pathway.

An indicative scope of work for the exploratory phase of the DSA is outlined as follows:

Table B Indicative Scope of Work – Detailed Site Assessment

Investigation Type	Indicative Number	Target Depth	Justification
Trial pit / slit trench	6	3 m bgl	Source Assessment - Assessment for the presence of contamination (including NAPL) in unsaturated and (if possible) saturated soil through collection of soil samples along the cable route, adjacent to and beyond the leak location. If possible, temporary monitoring wells could be installed into slit trenches to allow gauging of NAPL and completion of an indicative assessment of groundwater / soil vapour / ground gas quality.
Surface Water Monitoring	4	-	Receptor Assessment and Pathway Assessment – Collection of samples from the Grand Canal upstream and downstream of the leak location to assess for potential impact to surface water.
Desk based	-	-	Pathway Assessment – It is assumed that the Grand Canal adjacent to the site is lined with a low permeability material such as clay, as was commonly used in the 1700s - early 20 th Century to prevent leakage from the canal and thus loss of water level restricting navigation. Further desk based assessment to confirmed construction of Grand Canal.

An outline schedule of laboratory analysis is provided as follows:

Table C Preliminary Laboratory Schedule – Detailed Site Assessment – Exploratory Phase

Parameter	Number of Soil Samples	Number of Soil Leachate Samples	Number of Groundwater Samples	Number of Surface Water Samples
TPH Criteria Working Group Analysis	12	6	2	4
Extractable Petroleum Hydrocarbons	12	6	2	4
BTEX Compounds	12	6	2	4
VOCs & SVOCs	6	6	2	4
PCBs	6	6	2	4
Whole Oil Analysis	-	-	1 (if present)	-

Once the exploratory phase of the DSA is completed, recommendations can be made for further site investigation works required to assess potential SPR linkages identified as part of the PSA.

Yours sincerely,

██████████
Associate Director
AECOM Ireland Limited
T: +353 (0)1 238 3100
E: ██████████@aecom.com